


- A-ROUGH-IN WASTE AND SUPPLY LINES DURING -MP1 (1) INSTALLATION OR PRIOR TO MOUNTING FIXTURE.
- B-CAREFULLY REMOVE FIXTURE FROM PACKING MATERIAL AND COVER TO PREVENT SCRATCHING OR DAMAGE.
- C-REMOVE ACCESS COVERS (2) FROM HOUSING AND INSPECT FIXTURE TO ENSURE ALL TUBING CONNECTIONS, VALVES AND PUSHBUTTONS HAVE NOT BECOME LOOSE DURING SHIPPING. CORRECT IF NECESSARY.
- D-ALIGN FIXTURE MOUNTING POINTS WITH STUDS (3) AND SLIDE FIXTURE TO FINISHED WALL. FIX WITH NUTS AND WASHERS PROVIDED (4).


- E-MAKE UP CONNECTIONS TO 1-1/4" OD WASTE TEE (5) PROVIDED FOR P-TRAP ASSEMBLY BY OTHERS.
- F-FLUSH SUPPLY LINES THOROUGHLY BEFORE CONNECTING TO 3/8" NPT SUPPLY INLET (6).
- G-TEST OPERATION BY DEPRESSING BUTTON AND ADJUST FLOW RATE BY ADJUSTING 1/4 TURN SHUT OFF VALVE (7) AS REQUIRED. CHECK ALL PIPING FOR LEAKS. CORRECT IF PRESENT.
- H-ASSEMBLY ACCESS PANELS (2) TO COMPLETE THE INSTALLATION.

<b>M-OBA4 WALL MOUNTED BO</b>	<b>M-OBA4 WALL MOUNTED BOTTLE FILLER</b>		
MANUFACTURE DATE	DATE ISSUED	DRAWING NUMBER	
JUNE 2017	JULY 28, 2017		
TO PRESENT	DATE REVISED	9938-008-001	

## **DRINKING FOUNTAIN**

ROUGH-IN FOR 3/8" OD PUSH-IN SUPPLY INLET, STRAIGHT STOP RECOMMENDED. \*1/4" NCT x 2" LONG TUBE STUB OUT PROVIDED. ROUGH-IN FOR 1-1/4" OD P-TRAP WASTE OUTLET.





## **INSTALLATION INSTRUCTIONS**

3

- A-PLATE (1) INTENDED TO BE RECESSED FLUSH WITH SUPPORT FRAMING (2) PROVIDED BY INSTALLER. FRAME & BLOCK OUT SUPPORT USING DIMENSIONS SHOWN. FRAME SHOULD SUPPORT 300 LBS MINIMUM.
- B-MOUNTING PLATE (1) IS 1/4" THICK AND INCLUDES 12, 1/2" DIAMETER PUNCHING FOR ANCHORING HARDWARE BY OTHERS.
- C-STRIKE A HORIZONTAL CHALK LINE TO LOCATE BOTTOM MOUNTING HOLES ③. REFERENCE DISCHARGE HEIGHT REQUIREMENTS FOR YOUR MODEL AND FACILITY TO DETERMINE CORRECT HEIGHT AT FINISHED FLOOR (AFF).

- D-AFTER POSITIONING PLATE CORRECTLY, FIX PLATE TO WALL USING APPROPRIATE, INSTALLER PROVIDED ANCHORING HARDWARE (4).
- E-MAKE UP APPROPRIATE SUPPLY (5) AND WASTE
  (6) ROUGHS THROUGH MOUNTING PLATE OPENINGS.
  A STRAIGHT SUPPLY STOP IS RECOMMENDED.
- F-REFER TO FIXTURE INSTALLATION SHEETS TO LOCATE 5/16" THREADED STUDS MOUNTING HARDWARE AND THREAD STUDS ⑦ THRU PLATE SO THAT A MINIMUM OF 1-1/4" OF THREAD PROJECTS BEYOND THE FINISHED WALL MATERIAL.
- G-PROTECT THREADED STUDS (7), SUPPLY (5) AND WASTE (6) ROUGHS WHILE FINISHING WALL.

JANUARY 2006 To present	09/28/05 DATE REVISED 03/02/16	9938-375-001
	DATE ISSUED	. –